Pool Fittings ABS Inlets

Return Inlet ABS Threaded for Liner

Made in white ABS with 2" outer connection thread and Ø50 mm inner wall for liner pools . Supplied with gasket, screws and nut for liner fixing. Installed with female threaded wall conduits. Maximum Flow: 7 m³/hr. Recommended max. flow velocity 4 m/s.



01592828-3	Return Inlet ABS Threaded for Liner	12	

Suction Inlet ABS Threaded

Made in white ABS with 2" outer connection thread and Ø50 mm inner wall for concrete pools . Installed with female threaded wall conduits. Supplied with threaded plug of 1 1/2". Maximum pressure: 6 Bar



Code	Description	Stu packing	volume	
			(m³)	
01592827-2	Suction Inlet ABS threaded	24	0.020	

Suction Inlet ABS Threaded for Liner

Made in white ABS with 2" outer connection thread and Ø50 mm inner wall for liner pools . Supplied with gasket, screws and nut for liner fixing. Installed with female threaded wall conduits. Threaded plug of 1 1/2". Maximum pressure: 6 Bar.



Code	Description	Std packing	Volume
			(m³)
01592827-4	Suction Inlet ABS Threaded for Liner	12	0.020

Return Inlet ABS Threaded for Prefabricated

Made in white ABS with 2" outer connection thread and Ø50 mm inner wall for prefab pools . Supplied with gasket and rear nut for prefab pool fixing. Installed with female threaded wall conduits. Maximum Flow: 7 m³/hr. Recommended max. flow velocity 4 m/s.



Coue	Description	Stupacking	volume
			(m³)
01592836	Return Inlet ABS Threaded for Prefab	12	0.020

Suction Inlet ABS Slip Fit

Made in white ABS with Ø63 mm outer connection and Ø50 mm inner wall for concrete pools . Installed with internal glue type wall conduits. Supplied with threaded plug of 1 $1/2^{"}$. Max pressure: 6 Bar



Code	Description	Std packing	Volume	
			(m³)	
01592827	Suction Inlet ABS Slip Fit	24	0.020	

Suction Inlet ABS Threaded for Prefabricated

Made in white ABS with 2" outer connection thread and Ø50 mm inner wall for prefabricated pool . Installed with female threaded wall conduits. Threaded plug of 1 1/2". Supplied with gasket and rear nut for prefab fixing. Maximum pressure: 6 Bar.

